

#4

LEASE NAME Balthazor

WELL NUMBER 3

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 14 TWP. 9 RGE. 21W (E) or (W)

COUNTY Graham

Date Well Completed         

Plugging Commenced 12-27-93

Plugging Completed 12-30-93

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Lloyd Drilling Company

ADDRESS P. O. Box 59, St. Peter Rt., Morland, KS 67650

PHONE#(913) 627-5871 OPERATORS LICENSE NO. 3300

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1686'	none
				5 1/2	3730'	1820'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set. Sanded bottom to 3680' & spotted 5 sks cement. Shot @ 2119, worked pipe. Shot @ 1903, worked pipe, left on tension. Shot @ 1820, pulled sub & 3 jts. Spotted 12 gel, 1 hull, 50 cement. Pulled to 950, spotted 75 sks cement. Pulled to 450, mixed 40 sks cement & circulated to surface. Pulled rest of pipe, topped off w/15 sks cement. 60/40 pos 10% gel. Plugging complete.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lloyd Drilling Company

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1993

My Commission Expires:         

**IBENE HERZBERG**  
 Notary Public  
 State of Kansas  
 My Appl. Exp. Aug. 24, 1997

Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION  
 11/27/93  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 Revised 07-88