

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21441-00-00

LEASE NAME Knipp

WELL NUMBER 19

1650' Ft. from S Section Line

1650' Ft. from W Section Line

SEC. 14 TWP. 9S RGE 21 (W)

COUNTY Graham

Date Well Completed 9/1/81

Plugging Commenced 12/22/99

Plugging Completed 12/22/99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Benchmark Oil & Gas Corporation

ADDRESS 1515 Arapahoe Street, Suite 580, Denver, CO 80202

PHONE # (303) 595-9251 OPERATORS LICENSE NO. 31566

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Rich Williams (KCC District Agent's Name).

is ACO-1 filed? No if not, is well log attached? Previously submitted

Producing Formation Arbuckle Depth to Top 3724' Bottom 3766' T.D. 4004'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surf	267'	8-5/8"	267'	0'
		Surf	3845'	4-1/2"	3845'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
RU Chito's Well Svc. Run 66 jts tbg. Install stripper head on csg. RU Allied Cementing. Pump 75 sx 60/40 cmt w/10% gel x 200# hulls down tbg & circ to surf. POOH 8 jts tbg. Pump 65 sx cmt w/300# hull dwn tbg & circ to surf. POOH all tbg. Pressure up backside to 500#, held. Pump 100 sx cmt dwn csg @ max 1000 psi. ISIP 400 psi. RD Allied.

Name of Plugging Contractor Chito's Well Service / Allied Cementing License No. _____

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Benchmark Oil & Gas Corporation

STATE OF Colorado COUNTY OF Denver, ss.

Benchmark Oil & Gas Corporation (Employee of Operator) or (Operator) or

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Christa Trujillo

(Address) 1515 Arapahoe St., Suite 580, Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 19th day of January, 20 00

Manda M...
Notary Public

My Commission Expires 03/11/2002

My Commission Expires: _____

RECEIVED
STATE CORPORATION COMMISSION
1/21/00
JAN 21 2000

CONSERVATION DIVISION
Wichita, Kansas

USE ONLY ONE SIDE OF EACH FORM

Form CP-4