

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
245 North Water  
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD

Application to Dispose - March 29, 1955 Docket #

Graham County, Sec. 15 Twp. 9S Rge. 21 ~~22E~~ (W)  
Location as "NE/CNW/SW" or footage from lines 440 N - 440 W  
Lease Owner Conoco Inc.  
Lease Name O. E. Trexler Well No. 11  
Office Address 3817 NW Expressway, Okla. City, OK 73112  
Character of Well (completed as Oil, Gas or Dry Hole) S.W.D.  
Date well completed 5/9 19 55  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 1/6 19 84  
Plugging completed 1/6 19 84  
Reason for abandonment of well or producing formation not taking water as required.  
If a producing well is abandoned, date of last production N/A 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Dennis Hamel  
Producing formation N/A Depth to top N/A Bottom N/A Total Depth of Well 4135 feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Water	3720'	4131'	9 5/8"	280'	0
Granite Wash	Water	4131'	4135'	6"	3774'	0
				4 1/2" liner	3723'-4103'	0
Note: Disposing 46' below oil - water content.						
9 5/8" - cemented w/175 sks circulated to surface						
6" - cemented w/150 sks bottom D.V. tool @ 1672' cemented w/550 sks to surface.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

(1/6/84) State plugger on location, connected to 6" casing took injection rate. Pumped 50 sks 50/50 Poz-mix w/10% Gel, 3% C.C. 75# cello flakes, and mixed 2 - 100# sks of Hulls and pumped 250 sks of 50/50 Poz-mix w/10% Gel, 3% C.C. Minimum press 300#, Maximum press 700 P.S.I. ISIP - 700 P.S.I.

(1/7/84) Ran Measuring Line hit cement @ 129'. Ran top plug and dumped 1 sk cement on plug. Welded plate on top of casing.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing  
Address Box 69, Hays, KS 67601

STATE OF OKLAHOMA COUNTY OF OKLAHOMA ss.  
Dillon Anders (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dillon Anders  
3817 NW Expressway, Okla. City, OK 73112  
(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of February, 1984

My commission expires June 23, 1984

Martha K. Denham  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
2/10/84  
FEB 10 1984  
CONSERVATION DIVISION  
Wichita, Kansas