


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 15 Twp. 9 Rge. 21 ~~NE~~/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE SW



Locate well correctly on above
Section Plot

Lease Owner Sohio Petroleum Company
Lease Name Benson Well No. 5
Office Address Box 673, Russell, KS 67665
Character of Well (Completed as Oil, Gas or Dry Hole) Oil

Date Well completed December 14 1945
Application for plugging filed August 19 1977
Application for plugging approved August 23 1977
Plugging commenced September 3 1977
Plugging completed September 9 1977

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 3722'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1715'	None
				5 1/2"	3716'	2637'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand back to 3050' w/5 sx cement on top. Cement top at 3020'. Shot off and pulled 2637' of 5 1/2" casing. Put rubber plug in 8 5/8" casing, mixed 50 sx 50-50 Poz w/2% Gel, pumped in and followed w/36 BW, mixed 25 sx 50-50 Poz w/2% Gel, pumped in at 600#. Well P&A 9-9-77. Plugger on location.

9/20/77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling, Chase, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.
W. H. Ward (employee of owner) or ~~(owner or operator)~~


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Ward
Box 673, Russell, KS 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of September, 19 77

My appointment expires 9-28-79

Juanita Valentine
Juanita Valentine Notary Public.



CONTRACTOR'S VERIFIED LOG

Operator Schio Petroleum Co. Farm Name Benson Well No. 5
 Location SW/4 - 15-9-21
 Pool Name _____ County Graham State Kansas
 Commencement Date 10/26/45 Completion Date 11/14/45

LOG OF WELL

Depth		Formation	Deviation from Vertical (Degrees)	Remarks
From	To			
0	135	Sand, Shale, Shells		
135	465	Shale & Shells		
465	625	Shale, Sand, Shells		
625	655	Shale		
655	720	Sand		
720	805	Shale & Shells		
805	910	Sand & Shale		
910	1000	Sand, Shale, Shells		
1000	1050	Hard Sand, Shells		
1050	1090	Hard Sand		
1090	1140	Sand & Shale		
1140	1240	Shale & Shells		
1240	1430	Sand, Shells		
1430	1550	Shale, Sand, Red Bed		
1550	1705	Red Bed, Shale		
1705	1750	Anhydrite		
1750	2090	Shale & Shells		
2090	3250	Lime & Shale		
3250	3675	Lime		
3675	3710	Shale & Lime		
3710	3717	Shale		

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 23 1977
 CONSERVATION DIVISION
 Wichita, Kansas