

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 18 Twp. 9S Rge. 21W ~~(E)XXXXXX(W)X~~

Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner Peel-Hardman Oil Operators
Lease Name Sutor "B" Well No. 6
Office Address R. R. #3, Box 144B, Wichita 15, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed December 3, 19 50
Application for plugging filed December 9, 19 57
Application for plugging approved December 10, 19 57
Plugging commenced June 11, 19 58
Plugging completed June 14, 19 58
Reason for abandonment of well or producing formation No longer a commercial producer
If a producing well is abandoned, date of last production January 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well A. D. Fabricus
Producing formation Arbuckle Depth to top Bottom 3861 Total Depth of Well 3865 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	164	8 5/8"	164	None
		0	3862 1/2	5 1/2"	3862 1/2	2511

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

From 3865 to 3850 - Sand
From 3850 to 3820 - 5 sacks cement.
From 3820 to 500 - Heavy Rotary Mud
From 500 to 480 - Rock Bridge
From 480 to 400 - 25 sacks Cement
From 400 to 160 - Heavy Rotary Mud
From 160 to 150 - Rock Bridge
From 150 to 100 - 15 Sacks Cement
From 100 to 30 - Heavy Rotary Mud
From 30 to 0 - 10 Sacks Cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address Box 114, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
William Herbert (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
R. R. #3, Box 144B, Wichita 15, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of August, 19 58

My commission expires March 4, 1962.

[Signature]
Notary Public.

PLUGGING
FILE SEC 10 T. 9 R. 21W
BOOK PAGE 67 LINE 43

REC-20-58
CONSERVATION DIVISION
WICHITA, KANSAS

DRILLER'S LOG

Company: Peel-Hardman Producers

SW SW SE
Sec. 18 Twp. 9S Rge 21W

Farm: Sutor "B" Well No. 6

County: Graham,
Kansas

Total Depth: 3864'

Comm.: 11-18-50 Comp.: 11-27-50

Contractor: Glenn Peel Drilling Co., Inc.

Elevation:

Casing: 8 5/8" 164' Cem.

Production:

5 1/2" 3862.50' Cem.

Figures below indicate bottom of formations

Surface Clay	0 -	166
Shale & Rock		450
Shale		960
Sand		1080
Shale		1150
Shale & Red Bed		1400
Sand		1560
Shale		1780
Red Bed		1795
Anhydrite		1830
Shale & Shells		2000
Shale		2045
Salt & Shale		2135
Shale		2500
Lime		2590
Lime & Shale		3275
Shale & Shells		3338
Lime & Shal e		3530
Lime		3864
Total Depth		3864

This is to certify that the above information, is, to the best of our knowledge, true and correct.

Peel-Hardman Oil Operators

BY: Wm. Herbert

Subscribed and sworn to before me this 9th day of December, 1957.

My Commission Expires: June 4, 1959

Marian M. Herbert
Notary Public

