

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 - 1971
7-9-71
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Graham County, Sec. 18 Twp. 9S Rge. (E) 21 (W)

Location as "NE/CNW/SW" or footage from lines 330' FNL & 990' FEL
Lease Owner: Cities Service Oil Company
Lease Name: Seefeld "A" Well No. 7
Office Address: Box 553 Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole): Oil
Date well completed: 2-13 19 51
Application for plugging filed: 5-24 19 71
Application for plugging approved: 5-25 19 71
Plugging commenced: 6-15 19 71
Plugging completed: 6-15 19 71
Reason for abandonment of well or producing formation: Depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production: Dec. 1965
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Mr. W. L. Nichols
Producing formation: Arbuckle Depth to top: 3779' Bottom: 5' Pen. Total Depth of Well: 3784 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	280'	None
				5 1/2"	3780'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran in 1 sack hulls, 13 sacks cement filling from 3784' to 3650'.
Ran 27 sacks gel. 3650' to 950'; Ran 30 sacks cement 950' to 600',
3 sacks gel. 600' to 300' and ran 25 sacks cement from 300' to
surface. Pressure 1200 psi and shut-in pressure 700 psi.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor: Halliburton Company
Address: Hays, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
E. W. Peterman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. W. Peterman*
Box 553 Russell, Kansas 67665 (Address)

Subscribed and sworn to before me this 8th day of July, 1971

10-5-72



Notary Public.

WELL RECORD

Company Cities Service Oil Co. Well No. 7 Farm Seefeld
 Location 330' South and 990' West of NE Corner Sec. 18 T. 9 R. 21W
 Elevation 2252 (2249 Gr.) County Graham State Kansas
 Drlg. Comm. December 7, 1950 Contractor R. W. Rine Drilling Company
 Drlg. Comp. December 15, 1950 Acid None
 T. D. 3784' Initial Prod. Physical Potential: 160 oil, 25% water, 24 hrs. (2-12-51)

CASING RECORD:

8-5/8" @ 280' cen. 175 sx cement
 5-1/2" @ 3780' cen. 175 sx cement

FORMATION RECORD:

clay & shale	0-100
shale	280
shale & sand	1745
anhydrite	1760
shale & shells	1995
shale, shells & lime	2700
lime & shale	3110
lime	3640
lime & shale	3747
shale & chert	3774
lime	3779

3779 RTD = 3784 SLM

Corr. Top Lansing 3470 (-1021)
 Corr. Top Cherty Conglomerate 3752'
 Corr. Top Arbuckle 3779' (-1530)
 Penetration 5'
 Total Depth 3784' (-1535)

Fillup: 290' oil in 30 mins.
 1030' oil in 1-1/2 hrs.
 1575' oil in 2-3/4 hrs.
 2599' oil in 8-3/4 hrs.

SIFO: 500' 0°
 1000' 1°
 1500' 1°
 2000' 1°
 2500' 0°
 3000' 0°

7-7/8" rotary hole.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 25 1971
 CONSERVATION DIVISION
 Wichita, Kansas