

KANSAS

**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED  
STATE CORPORATION COMMISSION  
3-18-68  
MAR 18 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name I. O. Miller Oil Company

Complete Address: 619 Brown Bldg., Wichita, Kansas

Lease Name Pywell "A" Well No. 1

Location NW NW NW Sec. 35 Twp. 9 Rge. 20 (E) (W) X

County Rooks Total Depth ~~3803~~ 3813'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 11:30 A Day 12 Month 3 Year 1968

The Above well was plugged as follows:

Total Depth 3803' 8 5/8 csg set at 206' cwc

5 1/2 csg set at 3807' cw 150 sc cement.

Filled with sand to 3800' and dumped 5 sc cement with dump bailer.

Recov. 1000' of 5 1/2 csg.

Squeezed thru 8 5/8 plug container with 35 sc gel W/7 sc hulls, plg and 150 sc 50-50  
poz cement W/6% gel. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 3/18/68  
INV. NO. 7437-W

Signed: Leo F. Massey  
Well Plugging Supervisor