

DISTRICT CONSERVATION AGENT'S REPORT

60

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 74-37

LOCATION N $\frac{1}{2}$ SE SE

SEC. 35 TWP. 9 RGE. 20

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. C-7 Lease Wilson

Operator Francis Oil & Gas Address 905 Palace Bldg Tulsa, Okla

Field _____ County Rooks

Total Depth 3834 Feet.

Plugging Contractor Ace Pipe Pulling & Globe Cementing Co

Plugging Contractor's License No. 2

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 229' circulated with cement - 5 1/2" at 3822' with 125 sax
cement behind.

Filled with sand to 3800', set 4 sax cement with dump bailer, pulled
1180' 5 1/2" to 700', circulated hole with heavy mud (35 sax Gel),
displaced 20 sax cement through 5 1/2" at 600', heavy mud to 200',
displaced 20 sax cement through 5 1/2" at 200', heavy mud to 55', set
cementing plug, rock and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Edwin Petty
District Conservation Agent

Date 1-16-58

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1958
1-22-58
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
NL 35 T. 9 R. 20
BOOK PAGE 74 LINE 37