

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 67-43

LOCATION NE NE SE

SEC. 7 TWP. 9 RGE. 21

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Cooley

Operator Peel-Hardman Address R R #3 Box 144 Wichita, Kans

Field _____ County Graham

Total Depth 3790 Feet.

Plugging Contractor Bert Self Pipe Pulling

Plugging Contractor's License No. 48

Address _____
(Describe Briefly the manner in which the well was plugged)

8 5/8" at 190' circulated with cement - 5 1/2" at 3787'

Set 5 sax cement in bottom with dump bailer, pulled 2700'

5 1/2" - filled hole with heavy mud to 185', set rock and 15 sax

cement, mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
7/21/56
JUL 21 1956

CONSERVATION DIVISION
WICHITA, KANSAS

Edman
District Conservation Agent

Date 7-17-56

PLUGGING
FILE SEC 7 T 9 R 21w
BOOK PAGE 67 LINE 43