

KANSAS

2
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED

STATE CORPORATION COMMISSION

1/24/72
JAN 24 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Dreiling Oil, Incorporated,
 Complete Address R. R. #2, Victoria, Kansas.
 Lease Name Thompson Well No. 1
 Location SW-NE-NE Sec. 7 Twp. 9 Rge. (E) (W) 21
 County Graham Total Depth 3806'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated
 Plugging Contractor Above
 Address License No.
 Operation Completed: Hour 3:00 PM Day 20 Month 1 Year 1972

The above well was plugged as follows:

226'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 110 Cu. Ft. cement
thru DP from 950' to 625'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Nichols*
Well Plugging Supervisor

DATE 1-28-72

INV. NO. 5062-U