

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 129-53 County: Books
Location: NE NW SE Sec. 22 Twp. 9 Rge. 19 9 (E) (W)
Name of Field: Total Depth: 3600

I have this date completed supervision of plugging of:

Lease Name: Bartos Well No. B-1

Operator's Full Name: Sterling Drg Co

Complete Address: Box 127 Sterling, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Was any delay in plugging operations caused by Conservation Division Agent? Yes No

If yes how long? Reason:

Operation Completed: Hour 5PM Day 30 Month 9 Year 58

The above well was plugged as follows:

8 5/8" at 200' circulated with cement - 5 1/2" 3585' with 100 sax cement.
Filled with sand to 3570', set 4 sax cement with dump bailer, pulled
1185' 5 1/2" - circulated hole with heavy mud (Gel) through 5 1/2" at 600',
displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced
20 sax cement through 5 1/2" at 180', heavy mud to 55', set bridge and
10 sax cement to bottom cellar.
Mudding and cementing by West Supply Co's pump truck.

Signed: *Jedon Kelly*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

RECEIVED
STATE
10-7-58

PLUGGING
FILE SEC 22 T 9 R 19 W
BOOK PAGE 129 LINE 33