

RECEIVED
STATE CORPORATION COMMISSION

OCT 20 1959
10-20-59
CONSERVATION DIVISION
Wichita, Kansas

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks _____

Location: SE SW NE _____ Sec. 22 Twp. 9 Rge. 19 (E) (W) _____

Name of Field: _____ Total Depth: 3612

I have this date completed supervision of plugging of:

Lease Name: Bartos Well No. A-2

Operator's Full Name: Louie Lawrence

Complete Address: Box 448 Great Bend, Kans

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 12 Month 10 Year 59

The above well was plugged as follows:

8 5/8" 200' circulated with cement - 5 1/2" 3597' with 100 sax cement.

Filled with sand to 3580', set 4 sax cement with dump bailer, pulled 2790'

5 1/2" to 500', circulated hole with heavy mud (35 sax Gel), displaced 20

sax cement through 5 1/2" at 500', heavy mud to 180', displaced 20 sax cement

through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sax cement to bottom

cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 4/15/60

INV. NO. 762-20