

15-163-02965-00-01

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasMAY 7 1963
5-7-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sterling Drg Co

Complete Address: Box 127 Sterling, Kansas

Lease Name Bartos Well No. #2 SWD

Location SE NE SE Sec. 22 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3922

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Halliburton Cementing Co

Address: License No.

Operation Completed: Hour 12 No 0 Day 2 Month 5 Year 63

The Above well was plugged as follows:

8 5/8" 236' circulated with cement - 5 1/2" 3692' with 100 sax cement - DV
tool at 1526' circulated with cement 1526' to bottom cellar.
3400' 2 1/2" tubing lost in hole - cleaned out hole to 515' - lost hole at 515'

Run 2" tubing in hole to 515', circulated hole with heavy gel mud through
2" tubing, spotted 10 sax cement at 515' through 2" tubing - heavy mud to
250', displaced 10 sax cement through 2" tubing at 250', heavy mud to
40', cement 40' to 0'.

Mudding and cementing by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/7/63INV. NO. 7024-USigned: [Signature]
Well Plugging Supervisor