

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW SE ~~SW~~ ~~NE~~

SEC. 22 TWP. 9 RGE. 19

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Bartos 504 Ogleson Bldg

Operator Hathman & Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3639 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 157' circulated with cement - 5 1/2" at 3595'
with 100 sax cement behind.

Filled with chat to 3590', set 4 sax cement with dump bailer
pulled ~~3000'~~ 3000' 5 1/2", filled hole with mud to 157'
set rock and 15 sax cement, mud to 35', set rock and
10 sax cement to bottom cellar.

Edward Perry
District Conservation Agent

Date 7-24-52

RECEIVED
PLUGGIN CORPORATION COMMISSION
FILE SEC. 22 TWP. 9 RGE. 19
BOOK PAGE 33 LINE 27-26-52