

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,736-00-00 (of this well)

RECEIVED
NOV 10 1977
11-7-77
WICHITA, KANSAS

Operator's Full Name Graham-Michaelis Corp.

Complete Address Box 247, Wichita, Kansas

Lease Name Marcotte Well No. 1-22

Location NW SE SW Sec. 22 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3622'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 1 P Day 4 Month 11 Year 1977

The above well was plugged as follows:

RTD 3622' 8 5/8 csg set 250' cwc 175 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe, Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11-7-77

INV. NO. 6154-W

Signed: Leo Massey
Well Plugging Supervisor