


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 9-2

LOCATION NW SW SE

SEC. 13 TWP. 9 RGE. 21

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Balthazor

Operator ~~Phillips~~ Derby Oil Co Address Wichita, Kans

Field _____ County Graham

Total Depth 3841 Feet.

(Describe briefly the manner in which the well was plugged)

8 3/8" at 174' circulated with 125 sax cement - 4 1/2" at 3824'
with 125 sax cement behind - Lane Wells plugs to 3785' - Top Perf.,
at 3700'. These perforations squeezed off, perforated at 3680'.
Filled hole with sand to 3600', set 4 sax cement with dump bailer,
pulled 3200' 4 1/2", filled hole with mud to 175', set rock to 160'
with 10 sax cement on rock, filled with mud to 55', set rock
bridge and 10 sax cement to bottom cellar.

PLUGGING
 FILE SEC 13 TWP 9 RGE 21
 WELLS NO. 3

11-10-51

Edmund J. [Signature]
 District Conservation Agent

Date 11-4-51