


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 110-5

LOCATION N $\frac{1}{2}$ SW NE

SEC. 15 TWP. 9 RGE. 21

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease Eichman

Operator D. G. Hansen Address Logan, Kans

Field _____ County Graham

Total Depth 3717 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 260' circulated with cement - 5 1/2" at 3715' with
150 sax cement behind.

Filled with chat to 3710', set 5 sax cement with dump bailer,
pulled 2500' 5 1/2", filled hole with mud to 250', set rock
and 15 sax cement, filled with mud to 35', set rock and 10
sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
9-20-51
SEP 20 1951

[Signature]
District Conservation Agent

PLUGGING
FILE SEC 13 T 9 R 21
BOOK PAGE 110 LINE 5

CONSERVATION DIVISION Date 9-16-51
Wichita, Kansas