

KANSAS

JP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1967
6-7-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dane G. Hansen Estate,

Complete Address: Box #187, Logan, Kansas.

Lease Name Eichman Well No. 9

Location CS/2-S/2-~~SE~~4 NE/4 Sec. ¹³~~12~~ Twp. 9 Rge. (E) (W) 21 *w*

County Graham Total Depth 3777

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: C and G Drilling Company,

Address: 107 Rule Building, Wichita, Kansas. License No. _____

Operation Completed: Hour 12:15AM Day 3 Month 6 Year 1967

The Above well was plugged as follows:

201'--8 5/8" Surface pipe, cement circulated with 130 Sx.
Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.
cement thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and dis-
placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/7/67
INV. NO. 5352-W

Signed: *M. L. Nichols*
Well Plugging Supervisor