

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAR 3 1964
3-3-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Jenkins-Ray Supply,

Complete Address: Box # 967, Ponca City, Oklahoma

Lease Name H. Kolste Well No. 1

Location NE-NE-SE Sec. 16 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 4216

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Ca sing Pulling Company,

Address: Box # 405, Chase, Kansas License No. 436

Operation Completed: Hour 4:00PM Day 1 Month 3 Year 1964

The Above well was plugged as follows:

246'--13" Surface casing, cement circulated. 1487'--9 5/8" Intermediate string, cement circulated. 4034'--7" cemented with 600 Sx.

Set bridging plug @ 4010' and sanded back to 4000' and set 6 Sx. cement with dump bailer. Pulled 7" to 600' and circulated heavy gel mud, (used 24 Sx. gel). Pulled 7" to 540' and displaced 30 Sx. cement thru 7". Pulled 7" to 240' and displaced 30 Sx. cement thru 7". Pulled 7", set rock bridge @ 30' and 15 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. A. Nichols
Well Plugging Supervisor

DATE 3/3/64
INV. NO. 8430-W