

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: H & B Petroleum Corporation Address: PO Box 277, Ellinwood, Kansas 67526-0277 Phone: (620) 564-3002 Operator License #: 32158

Type of Well: Abandoned Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: by: (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) Arbuckle Depth to Top: 3810 Bottom: 3900 T.D.

20849-00-00 API Number: 15-163-20,324-0001 Lease Name: Marcotte Well Number: 1 Spot Location (QQQQ): SW - NW - SW - 3860 1650 Feet from North / South Section Line 660 49.50 Feet from East / West Section Line Sec. 26 Twp. 9 S. R. 20 East West County: Rooks 9/25/78 Date Well Completed: 09-25-1978 Plugging Commenced: 09-21-2007 Plugging Completed: 09-21-2007

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes a 'RECEIVED' stamp from the Kansas Corporation Commission dated OCT 03 2007.


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

- 1st plug 300 sx 60/40 Pos 4% Gel thru tubing @ 2350'
2nd plug 125 sx 60/40 Pos 4% Gel 400# hulls Cement circulated to surface
3rd plug 50 sx Down 8 5/8
4th plug 50 sx Down 5 1/2 Top off with 5 yds redi-mix to surface

Name of Plugging Contractor: Xtreme Well Service, Inc License #: 33369 Address: PO Box 337, Ellinwood, Kansas 67526-0337

Name of Party Responsible for Plugging Fees: H & B Petroleum Corporation State of Kansas County, Barton, ss.

Al Hammersmith, Vice President, H & B Petroleum Corporation (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature] (Address) PO Box 277, Ellinwood, Kansas 67526-0277

SUBSCRIBED and SWORN TO before me this 2nd day of October, 20 07 My Commission Expires: January 3, 2010

# ALLIED CEMENTING CO., INC.

28006

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>9-21-07</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION	JOB START	JOB FINISH
LEASE <u>Marcott</u>	WELL # <u>1</u>	LOCATION <u>Palco &amp; Red line</u>			COUNTY <u>Rooks</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)		<u>3/4 N E into</u>					

CONTRACTOR X Trane Well Service  
 TYPE OF JOB Old hole plug  
 HOLE SIZE \_\_\_\_\_ I.D.  
 CASING SIZE 5 1/2 DEPTH \_\_\_\_\_  
 TUBING SIZE 2 1/2 DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_

OWNER \_\_\_\_\_  
 CEMENT Used 5.25 sks 450 # h. 115  
 AMOUNT ORDERED 55 @ 60/45 w. 1  
600 # h. 115

**EQUIPMENT**  
 PUMP TRUCK CEMENTER Shane  
 # 366 HELPER John Roberts  
 BULK TRUCK  
 # 362 DRIVER Chuck  
 BULK TRUCK  
 # 378 DRIVER Chuck

COMMON	<u>315</u>	@	<u>11.10</u>	<u>3496.50</u>
POZMIX	<u>210</u>	@	<u>6.20</u>	<u>1302.00</u>
GEL	<u>21</u>	@	<u>16.65</u>	<u>349.65</u>
CHLORIDE		@		
ASC		@		
<u>Halls</u>	<u>5</u>	@	<u>25.50</u>	<u>127.50</u>
RECEIVED KANSAS CORPORATION COMMISSION				
		@	<u>OCT 03 2007</u>	
CONSERVATION DIVISION WICHITA, KS				
HANDLING	<u>551</u>	@	<u>1.90</u>	<u>1046.90</u>
MILEAGE	<u>94/sk/mile</u>	@		<u>2727.45</u>
				TOTAL <u>9050.00</u>

**REMARKS:**

2375' Trial to Circulate  
Cement mixed 300 sks  
Pulled up to 1063' mixed  
125 sks with 400 # h. 115 to  
Circulate Cement. Tied on  
to Buckside mixed 50 sks with  
50 # h. 115. Mixed 50 sks down  
5/2 casing

CHARGE TO: H & D  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

Thanks!

SIGNATURE Mike Hammersmith

**SERVICE**  
 DEPTH OF JOB \_\_\_\_\_  
 PUMP TRUCK CHARGE \_\_\_\_\_ 720.00  
 EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_  
 MILEAGE 55 @ 6.00 330.00  
 MANIFOLD \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 TOTAL 1050.00

**PLUG & FLOAT EQUIPMENT**

\_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 TOTAL \_\_\_\_\_

TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

Mike Hammersmith  
 PRINTED NAME

**COPY**