

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Bruce Oil Company, L.L.C.
Address: 1704 Limestone Rd, McPherson, Kansas 67460
Phone: (620) 241-2938 Operator License #: 5610
Type of Well: SWD Docket #: D-18,510
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9-24-07 (Date)
by: Steve VanGiesson (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Simpson SWD Depth to Top: 2690 Bottom: 2710 T.D. 2721

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 015-20,825 - 00 - 00
Lease Name: El Dorado Refinery
Well Number: 2
Spot Location (QQQQ): spot - SW - NE - NW
990 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 34 Twp. 25 S. R. 5 East West
County: Butler
Date Well Completed: 7-7-76
Plugging Commenced: 9-25-07
Plugging Completed: 9-26-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	soil, rock, shale	surface	241	8 5/8	241	none
Simpson	sand	2690	2710	5 1/2	2755	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Push wiper plug to top of tubing fish at 1880', put 7 sax of sand on top of wiper plug, filled hole with water, ran tubing to top of sand at about 1800', pumped 25 sax cement on plug, pulled tubing. Perforated 5 1/2 casing at 300' with four shots, removed plugs from 8 5/8 casing head, hooked pump truck to 5 1/2 casing, pumped cement down to perforations and circulated cement back to surface through 8 5/8 head, plugging completed.

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Cyclone Well Service License #: 3038
Address: P.O. Box 522, Canton, Kansas 67428-0522

OCT 03 2007

Name of Party Responsible for Plugging Fees: Bruce Oil Company
State of Kansas County, McPherson, ss.

CONSERVATION DIVISION
WICHITA, KS

Lonny Bruce (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Lonny Bruce

(Address) 406 Ponderosa Ct., McPherson, Kansas

SUBSCRIBED and SWORN TO before me this 1st day of October, 2007
Beverly A. Folck My Commission Expires: 12-13-09

Notary Public
State of Kansas
BEVERLY A FOLCK
My Appt. Expires 12-13-09

Handwritten initials