

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: 09/14/2007 (Date)
by: Darrel Dipman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing-Kansas City Depth to Top: 3768' Bottom: 3911' T.D. 3960'
Toronto Depth to Top: 3722.5' Bottom: 3725.5' T.D. 3960'

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 179-20542 - 00-01
Lease Name: Hardesty
Well Number: 1
Spot Location (QQQQ): _____ - N/2 - N/2 - NW
1650 4926 Feet from North / South Section Line
3630 4051 Feet from East / West Section Line
Sec. 20 Twp. 6 S. R. 26 East West
County: Sheridan *original date*
Date Well Completed: 11/21/1979 *6/30/94*
Plugging Commenced: 09/14/2007
Plugging Completed: 09/14/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing-Kansas City	Oil & Water	3768'	3911'	8.625"	360'	-0-
Toronto	Oil & Water	3722.5'	3725.5'	4.50"	3980'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated at 2245', 1500' and 420' with 2 shots. Ran tubing down to 2304'. Pumped 200 sx 60/40 Pozmix w/ 4% gel + 600 hulls. Pulled tubing up to 1150'. Pumped 100 sx 60/40 Pozmix w/ 4% gel + 150 hulls. Topped casing off with 5 sx 60/40 Pozmix w/ 4% gel. Pumped 65 sx 60/40 Pozmix w/ 10% gel + 50 hulls down annulus. Plugging complete on 09/14/2007 at 12: 45 p.m., witnessed and approved by Darrel Dipman with the KCC

Name of Plugging Contractor: Express Well Service & Supply Inc License #: 6426
Address: P. O. Box 31 Russell, KS 67665
Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.
State of Kansas County, Trego

Peter J. Fiorini - employee of Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *[Signature]*

(Address) P. O. Box 783188 Wichita, KS 67278-3188



SWORN TO before me this 1st day of October, 20 07

Joyce Cochran
Notary Public My Commission Expires: 4-10-11

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PPT

