

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Palomino Petroleum, Inc.
Address: 4924 SE 84th Street
Phone: (316) 799-1000 Operator License #: 30742
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: August 30, 2007 (Date)
by: Mike Wilson (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-079-00338-00-00
Lease Name: Eilert
Well Number: 2
Spot Location (QQQQ): NW-SW-SW-
1100' Feet from North / South Section Line
4990' Feet from East / West Section Line
Sec. 35 Twp. 24S S. R. 2 East West
County: Harvey
Date Well Completed: 01/15/1960
Plugging Commenced: 09/20/2007
Plugging Completed: 09/25/2007

*Per RBDMs
ACT*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Production	0'	2854'	4 1/2" 7.00	2854'	0'

*KCC PKT Per RBDMs
10/4/07*

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand off bottom to 2790' w/10 sxs cement. Could not get past 69' when trying to perforate. Go in hole w/2" tubing. Tag up at 69' - spin tubing w/tongs got tubing down to 150'. Hook up water truck to tubing - pump 10 bbl water & got tubing to go down. Ran to 330'. Pull out of hole with tubing. Perforate at 300'. Go in hole w/tubing to 300'. Run 1" pvc tubing down surface. Pump 250 sxs 60/40 poz mix w/4% gel. Circulated cement to surface. Pull out of hole w/tubing. Rig down.

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc. License #: 6901
Address: P.O. Box 231, Claflin, KS 67525
Name of Party Responsible for Plugging Fees: Palomino Petroleum, Inc.

OCT 04 2007

CONSERVATION DIVISION
WICHITA, KS

State of Kansas County, Barton, ss.

Joseph F. Strube (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/2010

(Signature) [Signature]
(Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED and SWORN TO before me this 3rd day of October, 20 07

Karen J. Mitchell My Commission Expires: 4/13/2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKS