

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form  
Form must be Signed  
All blanks must be Filled**

Lease Operator: Palomino Petroleum, Inc.  
 Address: 4924 SE 84th Street  
 Phone: (316) 799-1000 Operator License #: 30742  
 Type of Well: Oil Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: August 30, 2007 (Date)  
 by: Mike Wilson (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 079-00343 - 00 - 00  
 Lease Name: Eilert  
 Well Number: 7  
 Spot Location (QQQQ): SE - NW - SW - KCCPCT  
1650 Feet from  North /  South Section Line 10/4/07  
4290 Feet from  East /  West Section Line Per RBDMS  
 Sec. 35 Twp. 24S S. R. 2  East  West  
 County: Harvey  
 Date Well Completed: 12/22/1961  
 Plugging Commenced: 09/19/2007  
 Plugging Completed: 10/01/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0'	129'	8"	129'	0'
	Production	0'	2865'	5 1/2"	2865'	0' Per RBDMS

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pull out of hole 22' PR w/12' liner, 98 3/4" rods & 9 1" rods, 2-1/4" 40-ring valve. Pull out of hole w/88 jts 2-7/8" tbg w/2-1/2"x2-1/4"x15"x20' bbl. Had Perf Tech perforate at 250'. Sand well back to 2790' and top w/5 sxs cement. Go in hole w/2" tbg to 270'. Pump 90 sxs 60/40 poz mix w/4% gel. Circulated to surface. Pull out of hole w/tbg and rig down.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc. License #: 6901  
 Address: P.O. Box 231, Claflin, KS 67525

**RECEIVED -  
KANSAS CORPORATION COMMISSION**

**OCT 04 2007**

Name of Party Responsible for Plugging Fees: Palomino Petroleum, Inc.  
 State of Kansas County, Barton, ss.

CONSERVATION DIVISION  
WICHITA, KS

Joseph F. Strube (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

**KAREN J. MITCHELL**  
 Notary Public - State of Kansas  
 My Appt. Expires 4/13/2010

(Signature) Joseph F. Strube  
 (Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED and SWORN TO before me this 3rd day of October, 20 07

Karen J. Mitchell My Commission Expires: 4/13/2010  
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*PKT*