

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12/20/71
DEC 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company,
Complete Address Box #553, Russell, Kansas.
Lease Name Morel Well No. B-2
Location NW-SW-NE Sec. 22 Twp. 9 Rge. (E) (W) 21
County Graham Total Depth 3819'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Halliburton Services,
Address Box #339, Hays, Kansas. License No.
Operation Completed: Hour 10:30 AM Day 16 Month 12 Year 1971

The above well was plugged as follows:

152'--8 5/8" Surface casing, cement circulated with 100 Sx.
3808'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug back. Top per-
foration @ 3508'. 5 1/2" casing has been squeezed thru hole in casing @ 1050' to surface
with cement. No attempt to recover casing.

Squeezed 5 1/2" casing initially with 2 sacks hulls and 50 Cu. Ft. cement then 25 sacks
gel from 3600' to 1100' and followed with 75 Cu. Ft. cement from 1100' to 650' then
5 sacks gel from 650' to 175' and finally 25 Cu. Ft. cement from 175' to bottom of
cellar. Maximum pump-in pressure-850#. Final shut-in pressure-100#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 1-6-72
INV. NO. 4838-W