

KANSAS
STATE CORPORATION COMMISSION

15-065-01464-00-00

RECEIVED
STATE CORPORATION COMMISSION
10/11/61
OCT 11 1961
CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham
Location: SE SE NE Sec. 22 Twp. 9 Rge. (E) (W) 21
Name of Field: _____ Total Depth: 3777

I have this date completed supervision of plugging of:

Lease Name: Morel (B) Well No. 1

Operator's Full Name: Fender Pipe & Supply

Complete Address: Box 302 Russell, Kansas

Plugging Contractor: Barnes & Sons & Globe Cementing Co

Address: Russell, Kansas License No. 9

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 5 Month 10 Year 61

The above well was plugged as follows:

8 5/8" 210' circulated with cement - 5 1/2" 3775' with 125 sax cement.
Sand back to 3760', set 4 sax cement with dump bailer - pulled 1456' 5 1/2"
to 550', circulated hole with heavy gel mud through 5 1/2" - displaced 20
sax cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax cement
through 5 1/2" at 180', heavy mud to 35', set bridge and cement to bottom
cellar.

Mudding and cementing by Globe Cementing Co.

Signed: *Edna Petty*
Conservation Division Agent

Reviewed: *Harold Hollis*
Field Supervisor

Remarks:

INVOICED
DATE 10/13/61
INV. NO. 3845-W