

15-065-01463-00-90

KANSAS

Form CP-3  
Rev. 6-4-68

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
6/10/71  
JUN 10 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Cities Service Oil Company,  
Complete Address Box #553, Russell, Kansas.  
Lease Name Darnell Well No. A-6  
Location SE-NW-NW Sec. 22 Twp. 9 Rge. (E) (W) 21  
County Graham Total Depth 3770'  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Halliburton Services,  
Address Box #296, Hill City, Kansas. License No.         
Operation Completed: Hour 12:00 M Day 8 Month 6 Year 1971

The above well was plugged as follows:

275'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3767'--5 1/2" Production casing cemented on bottom with 100 Sx. DV tool set @ 1765'  
with cement circulated to surface.  
Squeezed well initially with 1 sack hulls and 20 Sx. cement to 3700' then 28 sacks  
gel from 3700' to 900' and followed with 120 Sx. cement from 900' to bottom of cellar.  
Maximum pump-in pressure--850#. Final shut-in pressure--300#.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 6-10-71

INV. NO. 3831-W