

KANSAS  
STATE CORPORATION COMMISSION  
ST.  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
8/3/60  
AUG 3 1960  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Graham  
Location: NW 1/4 Sec. 22 Twp. 9 Rge. 21 (E) (W)  
Name of Field: \_\_\_\_\_ Total Depth: 3805

I have this date completed supervision of plugging of:

Lease Name: Darnell Well No. 2  
Operator's Full Name: Cities Service Oil Co  
Complete Address: Bartlesville, Okla  
Plugging Contractor: C. E. Shull  
Address: Great Bend, Kans License No. 8  
Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_  
Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No   
If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 12 Noon Day 29 Month 7 Year 60

The above well was plugged as follows:

8 5/8" 160' circulated with cement - 5 1/2" 3801' with 100 sax cement and  
squeezed in dakota section with cement.  
Baker plug at 3750', set 4 sax cement on top plug with dump bailer, pulled  
650' to 500', pumped 30 sax mud through 5 1/2" at 500', displaced 20 sax  
cement through 5 1/2" at 500' - 900# pump pressure - pulled pipe and bailed  
hole down to 160', set rock bridge and 20 sax cement at 160', heavy mud  
to 40'. set rock bridge and 10 sax cement to bottom cellar.  
Mudding and cementing by Halliburton Co.

Signed: *Edmond Lott*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor *Sm*

Remarks:

INVOICED  
DATE 8-5-60  
INV. NO. 1748-W