

15-065-01459-00-00

Form CP-3
Rev. 6-26-62



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company.

Complete Address: Box # 553, Russell, Kansas.

Lease Name Darnall Well No. 1

Location App. CNE-NW Sec. 22 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3794'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Halliburton Services,

Address: Hays, Kansas. License No. _____

Operation Completed: Hour 1:00PM Day 24 Month 10 Year 1968

The Above well was plugged as follows:

156'--8 5/8" Surface casing, cement circulated with 125 Sx.

3792'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3770'. Top perforations @ 3491'. 5 1/2" casing squeezed from Anhydrite to surface.

Ran 2" tubing to bottom and displaced 40 Sx. cement thru tubing from 3770' to 3450'.

Pulled tubing to 3400' and circulated heavy gel mud using 25 sacks gel. Pulled tubing

to 1025' and displaced 45 Sx. cement thru tubing from 1025' to 665'. Pulled tubing

to 180' and displaced 10 Sx. cement thru tubing from 180' to 120'. Pulled tubing and

ran 5 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/28/68

INV. NO. 8721-W