

*40*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
4/29/63  
APR 29 1963

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Peel-Hardman Oil Operators  
Complete Address: R. R. #3, Box # 144-B, Wichita, Kansas.  
Lease Name Sutor "A" Well No. 2  
Location NE-NW-~~SE~~ Sec. 22 Twp. 9 Rge. (E) (W) 21  
County Graham Total Depth 3796  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Halliburton Oil Well Cementing Co.,  
Address:      License No.       
Operation Completed: Hour 9:30AM Day 23 Month 4 Year 1963

The Above well was plugged as follows:

195' 8 5/8" Surface pipe, cement circulated.  
3796' 5 1/2" Production casing.--Well had been squeezed from the Dakota  
sands, no attempt was made to recover production casing,  
Squeezed 5 1/2" casing with 40 sacks Halliburton gel mud followed with plug  
and 75 sacks Poz-Mix. Pump pressure at end of mixing Poz-Mix--300#.  
Final pressure after completion of plugging operations 100#.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 4/29/63  
INV. NO. 0946-W

Signed: H. L. Nichols  
Well Plugging Supervisor