

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 54-6
LOCATION C7N/2-SE-SW
SEC. 22 TWP. 9 RGE. 21

Dry Hole ☐ Abandoned Oil Well ☒ Abandoned Gas Well ☐

I have this date completed supervision of plugging of:

Well No. 3 Lease Sutor
Operator Derby Oil Co. Address Box 1030 Wichita Kans
Field County Graham
Total Depth 3815 Feet.
Plugging Contractor Bert Self
Plugging Contractor's License No. 48
Address Hutchinson Kans

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 318 C.W.C. 5 1/2" set 3813'
w/ 100 st Cem. Sanded hole to 3800' dumped
4 st Cem. Shot off and pulled 5 1/2" casing
Mud to 318' set rock bridge and run
15 st Cem. Mud to 35' rock bridge and
10 st Cem. to chase of cellar

8/19/54

CONSERVATION DIVISION
Wichita, Kansas

Warren D. Harner
District Conservation Agent

Date Aug 16, 1954

PLUGGING

FILE SEC 22 T 9 R 21 W
BOOK PAGE 54 LINE 6