

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
10/11/65
OCT 11 1965
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Drillers and Producers Pipe and Supply,
Complete Address: Box # 368, Hoisington, Kansas.
Lease Name Sutor Well No. A-1
Location NW-NE-^{SE}SW Sec. 22 Twp. 9 Rge. (E) (W) 21
County Graham Total Depth 3805
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Apex Casing Pulling Company, Incorporated,
Address: Box #368, Hoisington, Kansas. License No. 544
Operation Completed: Hour 2:00PM Day 6 Month 10, Year 1965

The Above well was plugged as follows:

156! -- 8 5/8" Surface pipe, cement circulated with 125 Sx.
3794! -- 5 1/2" Production casing cemented with 100 Sx. No perforations, no
plug back. 11! open hole.
Pulled 5 1/2" casing. Tied on 8 5/8" surface pipe and squeezed with 35 Sx.
gel followed with 75 Sx. cement. Final shut-in pressure 150#.
(Cementing and mudding operations performed by Halliburton Company)
(Recovered 840' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichol
Well Plugging Supervisor

DATE 10/11/65
INV. NO. 1957-W