


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 61-31
 LOCATION NW SW SE
 SEC. 22 TWP. 9 RGE. 21

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease Sutor

Operator Derby Oil Co Address Wichita, Kans

Field _____ County Graham

Total Depth 3816 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 285' circulated with 150 sax cement - 5 1/2" at 3811'
with 100 sax cement behind, and squeezed at 3217' with 150 sax
cement.

Filled with chat to 3890' set rock and 4 sax cement with dump bailer,
shot 5 1/2" at 2700', pumped in 195 sax Aquagel, 100 sax hulls and
3 bales Palco Seal, pulled 800' 5 1/2", set rock bridge at 280' and
15 sax cement, heavy mud to 35', set rock bridge and 10 sax cement
to bottom cellar.

RECEIVED
 STATE CORPORATION COMMISSION
 4/12/51
 APR 12 1951

Edon Lilly
 CONSERVATION DIVISION
 District Conservation Agent

Date 4-4-51

PLUGGING
 FILE SEC 22 T 9 R 21
 BOOK PAGE 61 LINE 31