

15-065-03399-00-03

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10/11/65
OCT 11 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Drillers and Porducers Pipe and Supply,
Complete Address: Box #368, Great Bend, Kansas.
Lease Name Sutor Well No. A-2
Location NW-NW-SE Sec. 22 Twp. 9 Rge. (E) (W) 21
County Graham Total Depth 4156
Abandoned Oil Well Gas Well Input Well SWD Well X D & A
Other well as hereafter indicated:
Plugging Contractor: Apex Casing Pulling Company, Incorporated,
Address: Box #364, Hoisington, Kansas License No. 544
Operation Completed: Hour 4:00PM Day 7 Month 10 Year 1965

The Above well was plugged as follows:

156'---8 5/8" Surface pipe, cement circulated with 125 Sx.
3825'---5 1/2" Casing cemented with 125 Sx. 5 1/2" perforated and squeezed
thru Dakota section.

Squeezed 5 1/2" with 35 Sx. gel followed by 75 Sx. cement. Well showed no
pressure at end of squeeze job. Shut well in. Ran measuring line after
24 hours and found top of cement @ 900'. Set bridge and filled hole to
80' with mud. Capped from 80' to bottom of cellar with 10 Sx. cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 10/11/65

INV. NO. 1958-4