

15-065-19016-00-00

Form CP-3
Rev. 6-26-62

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3/1/65
MAR 1 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Cities Service Oil Company,
Complete Address: Box #553, Russell, Kansas.
Lease Name Davignon Well No. 2
Location NW-NE-NW Sec. 20 Twp. 9 Rge. (E) (W) 21
County Graham Total Depth 3839
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Above
Address: License No.
Operation Completed: Hour 11:00AM Day 20 Month 2 Year 1965

The Above well, was plugged as follows:

--8 5/8" Surface pipe, cement circulated,
3836'--5 1/2" Production casing cemented. Top perforations @ 3520'. 5 1/2" squeezed
from 1100' to surface with 213 sacks cement.

Sanded well back to 3496' and set bridge with 3' rock and 2 Sx. cement
with dump bailer. Pushed plug to 550', set 24' bridge and 2 Sx. cement.
Set rock bridge @ 40' and 4 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Pichel
Well Plugging Supervisor

DATE 3/1/65

INV. NO. 744-W