

KANSAS

W STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
11/4/70
NOV 4 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company,
Complete Address Box #553, Russell, Kansas.
Lease Name Davignon Well No. A-1
Location NW-NW-NW Sec. 20 Twp. 9 Rge. (E) (W) 21
County Graham Total Depth 3832'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Halliburton Services,
Address Hill City, Kansas. License No.
Operation Completed: Hour 12:15 PM Day 2 Month 11 Year 1970

The above well was plugged as follows:

280'--8 5/8" Surface casing cement circulated.
3829'--5 1/2" Production casing cemented on bottom. (Open Hole Completion). 5 1/2" had
been squeezed and repaired twice in the Cedar Hills. No attempt to salvage.
Squeezed 5 1/2" casing initially with 1 sack hulls and followed with 25 Sx. cement then
28 sacks gel from 3800' to 1000' and followed with 125 Sx. cement from 1000' to 0.
Maximum pump-in pressure--1300#. Final shut-in pressure--500#.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 11/4/70
INV. NO. 2805-W