

KANSAS

*af*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
10/23/68  
OCT 23 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Specter Pipe & Supply, Incorporated,

Complete Address: Box #169, Russell, Kansas.

Lease Name Fury Well No. A-2

Location NW-NW-NE Sec. 20 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3812

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Lynch Casing Pulling Company,

Address: Route #4, Great Bend, Kansas. License No. 457

Operation Completed: Hour 12:15 PM Day 20 Month 10 Year 1968

The Above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated.  
3805'--5 1/2" Production casing cemented on bottom and squeezed from Anhydrite to surface.  
No indication of plug back or perforations.

Pushed plug to 3500', built sand bridge and set 5 Sx. cement with dump bailer. No  
attempt to pull 5 1/2" casing. Pushed plug to 1100', sanded to 1050' and filled hole to  
surface with 5 1/2 yards Redi-Mix cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Deibel*  
Well Plugging Supervisor

INVOICED  
DATE 10/23/68  
INV. NO. 8684-W