

KANSAS

TP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3/20/67
MAR 20 1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name Pricer Well No. 2

Location NW-NE-NW Sec. 19 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3864

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas License No. 346

Operation Completed: Hour 11:00AM Day 16 Month 3 Year 1967

The Above well was plugged as follows:

244'--8 5/8" Surface pipe, cement circulated with 175 Sx.
3858'--5 1/2" Production casing cemented with 175 Sx. Well plugged back to
3854'. Top perforations @ 3548'. Well squeezed in the Dakotas from 1165'
to surface with 165 sx. cement.

Pushed plug to 3500', sanded back to 3480' and set 5 Sx. cement with
dump bailer. Set rock bridge @ 400' and filled to surface with Redi-
Mix cement using 2 yards.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/20/67
INV. NO. 4930-W

Signed: M. L. Nichols
Well Plugging Supervisor