

VP

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2/4/69
FEB 4 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Eureka Drilling Company,

Complete Address: Box #157, Hamilton, Kansas.

Lease Name Fury Well No. B-2

Location SW-NE-NE Sec. 19 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3847'

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company, Incorporated,

Address: Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 12:30PM Day 2 Month 2 Year 1969

The Above well was plugged as follows:

280'--8 5/8" Surface casing, cement circulated with 175 Sx.
3840'--5 1/2" Production casing cemented on bottom with 175 Sx. Staging collar set in
Anhydrite with cement circulated to surface. Open hole completion.

Squeezed well with 2 sacks hulls initially and followed with 20 Sx. cement from 3847
to 3750' then 23 sacks gel from 3750' to 1050' and followed with 50 Sx. cement from
1050 to 650' then 5 sacks gel from 650' to 40' and finally 5 Sx. cement from 40' to
bottom of cellar. (Maximum pump in pressure-1000#. Final shut-in pressure-250#).

(Mudding and cementing operations performed by Globe Oil Well Cementing, Inc.,)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*
Well Plugging Supervisor

DATE 2/4/69
INV. NO. 9283-W