

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
2/4/69  
FEB 4 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Eureka Drilling Company,

Complete Address: Box #157, Hamilton, Kansas.

Lease Name Fury Well No. B-1

Location NE-NE-NE Sec. 19 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3856

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Company, Incorporated,

Address: Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 10:00AM Day 2 Month 2 Year 1969

The Above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3849'--5 1/2" Production casing cemented on bottom with 175 Sx. Well plugged back to 3854'.  
Open hole completion. 5 1/2" had been squeezed @ 1192' with 133 Sx. cement and @ 1234'  
with 119 Sx. cement.

Sanded well back to 3840' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and  
squeezed well with initially 21 sacks gel and followed with 50 Sx. cement from 1000' to  
600' then 9 sack gel from 600' to 240' and finally 80 Sx. cement from 240' to cellar.  
Maximum pump-in pressure-500#. Final shut-in pressure-200#. Recovered 618' 5 1/2" casing.  
(Mudding and cementing operations performed by Globe Oil Well Cementing, Incorporated).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Pichals  
Well Plugging Supervisor

DATE 2/4/69  
INV. NO. 9282-u