

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-065-01367-00-06

LEASE NAME Eichman

WELL NUMBER 3

2970 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 13 TWP. 9S RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 2/1/50

Plugging Commenced 10:15 A.M. 2/26/03

Plugging Completed 1:15 P.M. 2/26/03

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE# (7785) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 26, 2003 (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3712 Bottom 3717 T.D. 3717 P.B.T.D. 3712

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 3-3-03
 MAR 03 2003

KCC WICHITA

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	245'	None
				5 1/2"	3712'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Tubing at 3500', Mix 175 sks Gel and 25 sks cement with 200% Hulls and displace;
Mix 100 sks cement with 300% hulls at 1700', Top off 5 1/2" with 25 sks cement.
Hook on backside, Mix 50 sks cement. Shut in at 100 psi

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust


STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Richard L. Wallgren, Sr. (Employee of Operator) or (Operator) of above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Richard L. Wallgren, Sr. P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 27 day of February, 2003



Betty Jane Bittel Notary Public

My Commission Expires: July 17, 2004.

CONTRACTOR'S WELL LOG

Operator D. G. Hansen Farm Name Richman #3
 Location SE/4 SE/4 NW/4 Sec. 13-9-21W.
 Pool Name Morel, East County Graham State Kansas
 Commencement Date 1-18-50 Completion Date 2-1-50

LOG OF WELL

Elevation 2179' D.F.
 All measurements from the top of rotary bushing.

DEPTH FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	245			
245	795	Blue Shale	500' - 0°	
795	865	Red Bed		
865	922	Sand		
922	1000	Shale-Shells	1000' - 0°	
1000	1025	Shale-Shells		
1025	1385	Sand		
1385	1560	Shale-Red Bed		
1560	1682	Shale-Red Bed	1500' - 0°	
1682	1719	Anhydrite		
1875	2055	Shale-Lime	2000' - 0°	
2055	2230	Shale-Lime		
2230	2390	Lime		
2390	2510	Lime		
2510	2575	Lime		
2575	2690	Broken Lime-Shale		RECEIVED
2690	2790	Shale		MAR 03 2003
2790	2900	Shale		KCC WICHITA
2900	2980	Shale		
2980	3080	Shale		
3080	3130	Shale		
3130	3225	Lime-Shale		
3225	3295	Lime-Shale		
3295	3350	Lime-Shale		
3350	3402	Lime-Shale		
3402	3435	Lime		
3435	3443	Lime		Fishing.
3443	3450	Lime		
3450	3491	Lime		
3491	3499	Lime		
3499	3548	Lime		
3548	3590	Lime		
3590	3645	Lime		
3645	3700	Lime		
3700	3715	Lime		

CASING LEFT IN HOLE AFTER COMPLETION

Set 245.03' (8 jts.) 8-5/8" OD Surface casing.
 Ran 3728.43' (118 jts.) 5-1/2" OD Oil String of casing.
 STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of his knowledge and belief the above facts are true and correct.

G-C Drilling Company, Inc.

By R. E. [Signature], President

Subscribed and sworn to before me this 1st day of February, 1950.

My commission expires:
 June 25, 1951

[Signature]
 Notary Public