

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-30148-00-00

API NUMBER NA

LEASE NAME Andreson A

WELL NUMBER #14

1650 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 16 TWP 09 RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 4-24-97

Plugging Completed 4-24-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Black Diamond Oil, Inc.

ADDRESS P.O. Box 641, Hays, KS 67601

PHONE# 913625-5891 OPERATORS LICENS. NO. 7076

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well loc. attached? _____

Producing Formation Arbuckle Depth to Top _____ Bottom 3698 T.D. 3699

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>Lansing</u>				<u>8 5/8</u>	<u>752'</u>	<u>8</u>
<u>Arbuckle</u>				<u>5 1/2</u>	<u>3698'</u>	<u>8</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ran tubing to 1736 spot 80 sks 300# HULLS, pulled to 730
Mixed 60 sks @ 250# hull & circulated cement - tied on to 858
pumped 50 sks with 50# hull. Max 600 PSI - shut in at 150 PSI
tied on to 5 1/2 mixed 50 sks - max 1200 shut in at 100 PSI.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.


Kenneth Vehige (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 641

AND SWORN TO before me this 24th day of May, 19 97

Verda M. Brin
Notary Public



My Commission Expires: 7-18-99