

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-065-62901-00-00

Drilling completed

API NUMBER May, 1944

LEASE NAME Boland

WELL NUMBER #1 (SE NW NE)

4290 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 16 TWP. 9S RGE. 21 (E) (W)

COUNTY Graham

Date Well Completed May, 1944

Plugging Commenced 12-9-94

12:45 P.M.

Plugging Completed 12-9-94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS P.O. Box 352, Russell, KS 67665

PHONE# (913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 29, 1994 (date)

by District #4 (KCC District Agent's Name).

Is ACO-1 filled? Well drilled If not, is well log attached? Not available

Producing Formation Lansing/KC prior to inception of ACO-I
 Depth to Top 3503' Bottom 3581' T.D. 3692'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/KC	oil/water	3503	3581'	10-3/4"	180'	-0-
Arbuckle	oil/water	3674	3692'	5-1/2"	3674'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

The casing was perforated 2 shots @ 1775' and 2 shots @ 900' prior to cementing.

2-1/2" tubing @ 2319' - spotted 120 sks. cement w/200# hulls. Pulled to 1160' & circulated cement to surface w/130 sks. cement & 200# hulls. Came out w/tubing & hooked up to casing - squeezed in 50 sks. cement & 100# hulls @ 200# maximum PSI. Shut in @ 100# (OVER)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. 5135

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III

(Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John O. Farmer III


(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 19 94

Margaret A. Schulte

Notary Public
 Margaret A. Schulte

My Commission Expires:



(CONTINUED FROM REVERSE SIDE)

8-5/8" backside mixed 50 sks. cement w/100# hulls @ 200# maximum PSI & shut in.