


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 16 Twp. 9 Rge. (E) 21 (W)  
Location as "NE/CNW/SW" or footage from lines NW 1/4 NE 1/4 NW 1/4  
Lease Owner Barnett Oil Company  
Lease Name Boland Well No. 8  
Office Address 417 First Nat'l Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 16, 19 53  
Application for plugging filed May 16, 19 53  
Application for plugging approved May 16, 19 53  
Plugging commenced May 16, 19 53  
Plugging completed May 16, 19 53  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3821 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION      | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|----------------|---------|------|----|--------|--------|------------|
| Surface Casing |         |      |    | 8 5/8" | 138'   | None       |
|                |         |      |    |        |        |            |
|                |         |      |    |        |        |            |
|                |         |      |    |        |        |            |
|                |         |      |    |        |        |            |
|                |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3821 feet to 160 feet. Set wooden plug with 6 ft. rock bridge from 160 feet to 154 feet and cement from 154 feet to 106 feet. Filled surface casing with heavy mud from 106 feet to 40 feet. Set wooden plug at 40 feet and filled surface casing with 1/2 sack of hulls and ten sacks of cement to bottom of cellar.

6-4-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnett Drilling, Inc.  
Address 623 First Nat'l Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. R. Hunter (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Hunter  
417 First Nat'l Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 1953

My commission expires February 27, 1956. Mildred F. Willis Notary Public.

PLUGGING  
FILE SEC 16 T 9 R 21W  
BOOK PAGE 101 LINE 40

BARNETT OIL COMPANY  
LOG OF BOLAND WELL NO. 8  
NW $\frac{1}{4}$  NE $\frac{1}{4}$  NW $\frac{1}{4}$  SECTION 16-9S-21W,  
GRAHAM COUNTY, KANSAS

DATE COMMENCED: May 4, 1953

DATE COMPLETED: May 16, 1953

| Formation         | From | To   | Remarks  |
|-------------------|------|------|--|
| Clay              | 0    | 30   |  |
| Sandy Shale       | 30   | 60   |  |
| Sand              | 60   | 70   |  |
| Shale             | 70   | 205  | Set 8 5/8" Surface Pipe at 138 feet;<br>cemented with 125 sacks of cement. |
| Blue Shale        | 205  | 300  |  |
| Shale and Shells  | 300  | 955  |  |
| Shale             | 955  | 1130 |  |
| Sand              | 1130 | 1120 |  |
| Red Bed and Shale | 1120 | 1530 |  |
| Shale             | 1530 | 1685 |  |
| Anhydrite         | 1685 | 1730 |  |
| Shale and Shells  | 1730 | 2135 |  |
| Lime              | 2135 | 2510 |  |
| Lime and Shale    | 2510 | 2855 |  |
| Lime              | 2855 | 2925 |  |
| Lime and Shale    | 2925 | 3245 |  |
| Lime              | 3245 | 3305 |  |
| Lime and Shale    | 3305 | 3450 |  |
| Lime              | 3450 | 3722 |  |
| Cherty Lime       | 3722 | 3821 |  |
| Total Depth       |      | 3821 | Dry and Abandoned.   |

RECEIVED  
STATE COMMISSION OF GEOLOGICAL AND MINERAL SURVEY  
MAY 15 1953  
CONSULTING DIVISION

**PLUGGING**  
FILE SEC 16 T 9 R 21W  
BOOK PAGE 101 LINE 40