

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 16 Twp. 9 Rge. 21 ~~22~~ (W)

Location as "NE/CNW/SW" or footage from lines NW 1/4 SE 1/4 NW 1/4

Lease Owner Barnett Oil Company, et al

Lease Name Boland Well No. 9

Office Address 417 First National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 24 19 54

Application for plugging filed September 24 19 54

Application for plugging approved September 24 19 54

Plugging commenced September 24 19 54

Plugging completed September 24 19 54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3765 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	148'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud from 3765 feet to 145 feet. Set plug at 145 feet and dumped 15 sacks of cement. Filled surface casing with mud to 40 feet. Set plug at 40 feet and filled casing with cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnett Drilling, Inc.

Address 623 First National Bank Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
A. D. Barnett (employee of owner) (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) A. D. Barnett

417 First National Bank Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of September, 19 54

Oliver Carter Notary Public.

My commission expires March 21, 1955



BARNETT OIL COMPANY  
 LOG OF BOLAND WELL NO. 9  
 NW $\frac{1}{4}$  SE $\frac{1}{4}$  NW $\frac{1}{4}$  Section 16-9-21W  
 GRAHAM COUNTY, KANSAS

DATE COMMENCED: September 11, 1954

DATE COMPLETED: September 24, 1954

Formation	From	To	Remarks
Surface Clay	0	30	
Sand	30	60	
Shale	60	90	9-11-54
Sand	90	110	Set 8 5/8" O.D., 8rd Thd. 2 1/2"
Shale & Shells	110	118	surface casing @ 118 ft. R.B. Cemented with 125 sac cement.
Shale	118	735	
Shale and shells	735	1165	
Sand	1165	1110	
Shale and shells	1110	1125	
Shale	1125	1665	
Anhydrite	1665	1710	
Shale and shells	1710	2100	
Lime and shale	2100	2385	
Shale and lime	2385	2555	
Lime and shale	2555	2760	
Shale	2760	3000	
Shale and Lime	3000	3210	
Lime and shale	3210	3305	
Lime	3305	3640	
Lime and shale	3640	3715	
Lime	3715	3765	
Total Depth		3765	

**PLUGGING**  
 WELL NO. 16-9-21W  
 BOOK PAGE 66 LINE 30