


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Russell County. Sec. 22 Twp. 9 Rge. 21 (E) W (W)
Location as "NE/CNW/SW" or footage from lines 1370 ft S & 300 ft W NE
Lease Owner Allen T. Fender
Lease Name Allen T. Fender - Morrell Well No. B-1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced Aug 21 1961
Plugging completed Oct 5, 1961
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3777 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3777 feet to surface feet for each plug set.

Hole filled with sand from 3777 to 3765 (no preforations-2 ft open hole) Pipe shot off at 1463 10 and pulled to 550 ft; Hole then circulated with mud, and 20 sacks of cement pumped down to 550 feet. Pipe then pulled to 180 ft, and 20 sacks of cement pumped down to 180 ft; all pipe pulled and hole capped with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
11/20/61
NOV 20 1961
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnes and Sons Pine Pulling Co.,
Address Russell, Kansas.

STATE OF Kansas, COUNTY OF Russell, ss.
Allen T. Fender (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allen T. Fender
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 61

Ruth Phillips
Notary Public.

My commission expires May 26, 1963



L RECORD

COMPANY: Cities Service Oil Co. WELL NO.: 1 FARM: Morel "B"
 LOCATION: 1370' south & 330' west of NE Corner Sec. 22 Township 9 Range 21W
 ELEVATION: 2277' COUNTY: Graham STATE: Kansas
 DRIG. COMM: November 24, 1941 CONTRACTOR: Hissom Drilling Company
 DRIG. COMP.: December 13, 1941 ACID: None
 TOTAL DEPTH: 3777' INITIAL PROD. Echometer Potential: 3000 oil, no water, 24 hrs.
Ind. cap. 15,890 bbls.

CASING RECORD:

8-5/8" @ 210' cem. 150 sx Red Ring
 and 1 sx C. C.
 5-1/2" @ 3775' cem. 125 sx Victor

Corr. Top Arbuckle 3774'
 Penetration 3'
 Total Depth 3777'

FORMATION RECORD:

surface sand	0-110
shale & shells	210
shale	538
shale, shells & sand	1104
sand	1137
lime shells	1139
shale & shells	1290
sand	1400
red bed, shale & shells	1500
shale & lime	1653
red shale	1718
anhydrite	1761
shale & shells	2025
shale	2126
shale & shells	2188
broken lime	2260
lime	2268
broken lime	2300
shale & lime shells	2397
shale & lime, broken	2430
lime	2500
broken lime	2650
shale & lime	2806
lime	2853
sandy lime	2874
lime	2946
shale	3054
lime & shale	3215
shale	3283
lime	3702
lime & shale broken	3736
lime	3753
shale	3779
lime	3780

Fillup: 2950' oil in 45 mins.

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 20 1941
 CONSERVATION DIVISION
 Wichita, Kansas

3780 Rot. TD = 3775 SIM
DOLEMITE

3777 T.D.