

15-065-01462-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15- NA
LEASE NAME Darnell A
WELL NUMBER #4

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

2970
~~4950~~ ZAP ft. from S Section Line
4290 KCC
~~390~~ ft. from E Section Line

LEASE OPERATOR OXY USA INC.
ADDRESS P.O. Box D, Plainville, KS 67663
PHONE # 785-434-7681 OPERATOR'S LICENSE NO. 5447
Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply)

Spot Location - - -
SEC 22 TWP 9 S RGE 21 (W) or (W)
COUNTY Graham
Date Well Completed 3-12-46
Plugging Commenced 12-8-97
Plugging Completed 12-10-97

The plugging proposal was approved on 11-4-97 (date)
by David P Williams - Hays, KS (KCC District Agent's Name)

Is ACO-1 filed? On File If not, is well log attached? _____
Producing Formation Arbuckle Depth to Top 3751 Bottom 3755 T.D. 3755

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in	Pulled out
		5'	147'	8-5/8"	147'	0'
		0'	3751'	5-1/2"	3751'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

*** See back for details ***

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. NA
Address Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA INC.

STATE OF Kansas COUNTY OF Rooks, ss.
J.D. Hininger (Employee of Operator) or (Operator) of above-described well, being first duly sworn

on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J.D. Hininger
(Address) P.O. Box D, Plainville, KS

STATE CORPORATION COMMISSION


12/31/97
DEC 31 1997

SUBSCRIBED AND SWORN TO before me this 12th day of December, 1997

CONSERVATION DIVISION

Sheryln Axelson Notary Public

My Commission Expires:
5-20-2000



OXY U.S.A., Inc.
Well Chronological Report

12/30/97

DARNELL 4

12/17/97 JOB: Plug and Abandon; CMIC: George Younger
12/08/97 - Plug and Abandon - Pumped 25 sks - 60/40 pozmix plus 10% gel
and 100 lbs. of hulls dn 8 5/8 shut in w/75 psi. - Pumped dn 5 1/2"
w/200 sks and 150 lbs. of hulls - well on vac. - shut in -
12/10/97 - Mixed and pumped 60 sks and 100 lbs. of hulls - 5 1/2"
stayed full. State witness Dennis Hamel - P&A 10:45 AM 12/10/97
12/16/97 - Cut off csg. - cleaned up location. - complete
L/E \$ 897; MAT \$ 1950; CUM: L/E \$ 897, MAT \$ 1950;

STATE COMMISSION

DEC 31 1997

CONSERVATION DIVISION
VT. DEPT. OF CONSERVATION