

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67226 67202

WELL PLUGGING RECORD  
K.A.R. -82-3-117

API NUMBER 15-065-02920-00-00  
LEASE NAME Darnell  
WELL NUMBER A #3  
4950 Ft. from S Section Line  
4290 Ft. from E Section Line

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR VESS OIL CORPORATION  
ADDRESS 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226  
PHONE # (316) 682-1537 OPERATOR'S LICENSE NO. 5030  
Character of Well Oil

SEC. 22 TWP. 9 RGE. 21 (E) of (W)  
COUNTY Graham  
Date Well Completed 9/18/45  
Plugging Commenced 2/17/99  
Plugging Completed 2/17/99

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/2/98 (date)  
by David Williams (KCC District Agent's Name)

Is ACO-1 filed? no If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3776 Bottom 3780 T.D. 3780

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	203	
				5-1/2	3776	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Perforated @ 1740' and 1000'. Ran tubing to 3720'. Spotted 20 sx gel and 25 sx cement w/150# hulls.

Pulled to 1740' and spotted 40 sx cement w/100# hulls. Pulled to 1000' and spotted 70 sx cement. Pulled tubing. Pumped down 5-1/2 csg w/25 sx cement. Pressured to 600#; SIP - 500#. Pumped down 5-1/2 and 8-5/8" annulus w/25 sx cement and 50# hulls. Pressured to 200#; SIP - 100#. Cement used was 60/40 Poz w/10% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_

Address P.O. Box 31, Russell, KS 67665-0031

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: VESS OIL CORPORATION

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Pat Canaday (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says that: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of February, 19 99

My Commission Expires:



Notary Public

Form CP-4  
Revised 05-88

FILED  
2/23/99  
Graham County, Kansas

Company Cities Service Oil Co. Well No. 3 Farm Darnell  
 Location 330' South and 990' East of NW Corner Sec. 22 T. 9 R. 21W  
 Elevation 2279 County Graham State Kansas  
 Drig. Comm. September 6, 1945 Contractor Hola Drilling Company  
 Drig. Comp. September 18, 1945 Acid None  
 T. D. 3780' Initial Prod. Depthograph Potential: 1140 oil, 0 water, 24 hours

GASING RECORD:

8-5/8" @ 203' con. 150' ex bulk con.  
 and 2 ex C. O.  
 5-1/2" @ 3776' con. 100' ex bulk con.

FORMATION RECORD:

collar	0-7
sand	35
clay	80
shale	170
sandy shale	190
shale	840
sand	1075
shale	1120
lime	1125
shale & shells	1290
sand	1400
shale	1475
shale & lime shells	1550
shale red	1735
lime & gyp	1770
gyp & shale	1825
shale	2165
lime	2180
lime & shale	2250
shale & shells	2304
lime & shale	2350
lime broken	2400
shale & lime shells	2460
lime & shale	2560
shale & shells	2575
lime broken	2735
shale & lime shells	2765
lime broken	2795
lime	2805
lime broken	2835
lime	2855
shale	2880
lime broken	2905
lime	2995
broken lime & shale	3025
lime & shale	3060

shale & lime shells	3365
lime	3390
lime & shale	3435
lime	3765
shale	3775
lime	3780

3780 Rot. TD = 3780 SLM

Top Arbuckle	3775'	-1496
Penetration	5'	
Total Depth	3780'	

Fillup: 210' oil in 20 minutes  
 700' oil in 1-3/4 hours  
 900' oil in 2 hours  
 1980' oil in 3-1/4 hours  
 2350' oil in 4-3/4 hours  
 2800' oil in 9-1/4 hours

SYFO:	500'	1°
	1000'	0°
	1500'	1°
	2000'	0°
	2500'	1°
	3000'	0°
	3500'	0°

RECEIVED  
 KANSAS CORP. CO.  
 1945 SEP 20 11 33