

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CONSERVATION COMMISSION
NOV 7 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Johnny Crowe of Garvey Drilling Company has this
date requested permission to plug the following described well:
Petroleum, Inc.
Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name: Balthazor Well No. C-1

Location: N/2-SE-SW Sec. 12 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3721 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

213' -- 8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulate hole with heavy mud, set plug @ 540' and 25 Sx. cement.

" " " 210' and 20 Sx. cement.

" " " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

K. L. Nichols
Conservation Division Agent