

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Tom Alm of Pioneer Well ^{W/c # 256} has this date requested permission to plug the following described well:

Operator's Full Name: Liberty Enterprises Inc ^{W/c # 5562}

Complete Address: 308 West Mill, Plainville, Mo. 67663

Lease Name: Baltazor Well No. #1

Location: NE-SW-SW Sec. 12 Twp. 9 Rge. 21 (E) (W)

County: Graham Total Depth: 3736 ^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: ..

Mr. Alm was instructed to plug the well as follows ^(By Alled)

8 5/8" - 209 FT SR. CCL w/ 130ST 60/40 Formid - 2% Gel - 3% Ca.Cl.
Order 200ST 50/50 Formid 6% Gel - 3% Ca.Cl. and 8 5/8" Plug
Spot with Ball Stem - with Heavy mud Between all Plugs
1ST Plug @ 3660^{FE} w/ 20ST Ont. → 2ND Plug @ 1650^{FE} w/ 20ST Ont.
3RD Plug @ 870^{FE} w/ 100ST Ont. → 4TH Plug @ 240^{FE} w/ 40ST Ont.
5TH Plug = Scaled Bridge - Plug @ 40^{FE} 100ST w/ 10ST Ont. → 10ST In Out Hole (circulate)

Very truly yours, ^(By Alled Ont)

RECEIVED
STATE CORPORATION COMMISSION

Marion J. Schmidt
Conservation Division Agent

OCT 1 1982
10/19/82
CONSERVATION DIVISION
Wichita, Kansas